



- WALL**
- WA-01 BRICK VENER WALL WITH 92MM STEEL STUD & 13 PB LINING BRADFORD GOLD HI PERFORMANCE WALL BATTS R2.7 90MM THICK THICKNESS 235MM
 - WA-02 90MM CONCRETE BLOCK WALL TO MATCH EXISTING THICKNESS 90MM
 - WA-03 76MM STEEL STUD PARTITION WITH 13M PB LINING BOTH SIDES. BRADFORDS SOUNDCREEN R2.0 70MM THICK INSULATION THICKNESS 102MM
 - WA-04 CAPRAL 400 SERIES GLAZING PARTITION GLASS TO CODE THICKNESS 102MM
 - WA-05 13MM PB DIRECT STICK TO EXISTING WALL

GROUND FLOOR PLAN
1:100 @ A1

- GENERAL NOTES**
1. ALL DIMENSIONS SHALL BE CHECKED ON SITE PRIOR TO CONSTRUCTION.
 2. MAKE GOOD EXISTING BUILDING AREAS THAT ARE IMPACTED OR MODIFIED DUE TO UPGRADE
 3. ALL ARCHITECTURAL DRAWINGS SHOULD BE READ IN CONJUNCTION WITH SPECIFICATIONS AND ENGINEERING DRAWINGS
 4. ANY DISCREPANCIES SHALL BE REPORTED TO DPTI BEFORE PROCEEDING WITH WORKS

A 06.06.17 BRC ISSUE SB
REV. DATE AMENDMENTS INIT.

Government of South Australia
Department of Planning,
Transport and Infrastructure

© COPYRIGHT - GOVERNMENT OF SOUTH AUSTRALIA - DPTI
SETTING OUT OF THE WORK IS THE RESPONSIBILITY OF THE CONTRACTOR
ALL DIMENSIONS TO BE VERIFIED ON SITE
DISCREPANCIES TO BE REPORTED IMMEDIATELY TO THE SUPERINTENDENT
THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER CONTRACT DOCUMENTS

CONTRACT EXECUTION DATE
CONTRACTOR _____

WITNESS DATE

CONTRACT NAME
STEM WORKS
PARAFIELD GARDENS HIGH SCHOOL

SITE ADDRESS
15 SHEPHERDSON ROAD
PARAFIELD GARDENS SA 5107

DRAWING TITLE
BUILDING 2
GROUND FLOOR PLAN

CONTRACT NO. 6279-PC-2016 DRAWN BY - CHECKED BY SB

PSC JOB NO. 28016 SCALE AND SHEET SIZE 1:100 @ A1

DPTI ASSET NO. 01137 SHEET NO. W04

DPTI DRAWING NO. 6783-AR-2017 REVISION